



Telephones:
Off.(PBX) : 0184-2291119,
 : 2291519 , 2291218
Fax : 91-184-2290480
E-mail-directr@cssri.ren.nic.in

केन्द्रीय मृदा लवणता अनुसंधान संस्थान,
करनाल (हरियाणा), भारत
Central Soil Salinity Research Institute,
Karnal- 132 001 (Haryana) INDIA

TENDER FORM

Sub.: TENDER IS INVITED FOR SUPPLY ,INSTALLATION, TESTING AND COMMISSIONING OF 8 PASSENGERS CAPACITY LIFT AT CSSRI, KARNAL AS PER ATTACHED DETAILS .

You are hereby invited to submit the rates for the work on the above subject as per details attached and as per terms & conditions below. Tender should be sealed comprising of two parts, viz. Technical and Financial and should follow the conditions i.e. Technical and Financial proposals must be submitted in two separate sealed envelopes (with respective marking in bold letters). Unsealed tenders are liable to be rejected. The sealed tenders in two different envelopes giving reference of work on the body of envelope as per guidelines must reach at this Institute **on or before 11.8.2010** in the name of Sr. Admn. Officer, CSSRI, Karnal – 132 001 (Haryana) The tenders will be opened by the authorized committee constituted by the Director in the presence of tenderers or their representatives (if they wish so) at 3.00 P.M. on **12.8.2010**. A two stage procedure will be adopted in evaluating the proposals (i) a technical evaluation , which will be carried out prior to opening any financial proposal (ii) a financial evaluation .

SPECIFICATION

Load –Kgs	About 544 Kgs (8 Passenger)
Speed	1.00 MPS
Travel	11 Mts. approx
Stops &Opening (Max)	Ground ,1 st Floor to 3 rd Floor (4 stops 4 openings) All opening on same side
Power Supply	400 Volts 3 phase 50 Hertz. Alternating Current
Control	AC Variable Voltage Variable Frequency with Close Loop
Operation	Simplex Full collective with/without attendant
Machine	Geared placed directly above the hoistway in machine room
Car Size	1300mm wide x 1100 mm Deep
Hoistway Required	About 1900 mm wide x 1800 mm deep inside dimensions.
* Car Entrance	Protected by Center Opening Sliding Steel Doors in Powder Coated Finish Clear Opening about 800 mm wide x 2100 mm high
* Hoistway Entrance	Protected by Center Opening Sliding Steel Doors in Power Coated Finish

	Clear Opening about 800 mm wide x 2100 mm high
* Handrail on Sides	Stainless Steel Mirror Finish
* Car Panels	Front Return – SS hairline, Rear and Side Panels – Powder Coated.
* Car Enclosure	
* False Ceiling	HSET No 8
* Flooring	PVC
Door Operation	Automatic with ACVVVF Door Operator & Infra Red Electronic Door Protection
Signal Design	GIEN
Details	<ol style="list-style-type: none"> 1. Combined Luminous Hall Button with 16 Segment Digital Hall Position Indicator at all Landings. 2. Car Operating Panel with Luminous Buttons, 16 Segment Digital Car Position Indicator Combined with Direction Errors, Overload Warning Indicator 3. Battery operated alarm bell and emergency light. 4. Fireman switch at main lobby
Face Plate Finish	Stainless Steel in Hairline

जम्है – ब्छवप्पुव्छैरु

- 1^प |जिमत जीम वृता पे बवउचसमजमक जीम पजमी जव इम बसमंतमक दक बसमंदमक
- 2^प |दल जलचम विविपिबपंस पउचसमउमदजे दकीमसचूपसस दवज इम चतवअपकमक इल जीम विपिबम
- 3^प |सस चतमबंनजपवदंतल मिजल उमंनतमेी जव इम विससवूमक – तपो पिदल पे जव इम इवतद इल जीम बवदजतंबजवत
- 4^प विपिबमूपसस दवज इम तमेचवदेपइसम वित दल उपेीचचमदपदह पिबनेमक कनतपदह जीम मगमबनजपवद वि वृता जव जीम बवदजतंबजवत वतीपे वृतामते
- 5^प जीम जिमत दक मसमबजतपबपजल बेंतहमे पिनेमक विजीपे विपिबम / 1: 1: विजीम जवजंस अंसनमूपसस इम कमकनबजमक तिवउ पिदंस इपसस
- 6^प दबवउम जं चचसपबंइसमूपसस इम कमकनबजमक तिवउ लवनत इपसस
- 7^प जीम चलउमदजूपसस इम उंकम वदसल वद इपसस इंपे

8. The tenders must be accompanied with EMD with technical specifications for Rs. 28,000/- in the shape of Bank Draft drawn in favour of ICAR-UNIT-CSSRI, Karnal. Cash and cheques are not allowed & will not be accepted.

9. The 5-10% as performance Security money of the total amount have to be deposited by the concerned bidder after the allotment of work & before the start of work. However, EMD amount can be adjusted against the Security amount with the approval of the Competent Authority.
10. The work must be completed within Two months from the date of the issue of Work order. A penalty may be imposed as per GFR i.e. minimum of 2% in case the Work is not completed within stipulated time.

11. Bills on actual measurement basis will be passed after satisfactory certificate of the Committee Constituted by the Competent Authority.

12. The rates must be quoted net per unit.

13. Director, CSSRI, Karnal has the right to cancel the Tender without assigning any Reason.

14. PAN NO. , BANK's NAME & BANK ACCOUNT NO. MUST BE RECORDED ON THE TENDER POSITIVELY. ---REPEATED

15. Every tender must be accompanied by a certificate as : Photostate copy, duly attested of the sales tax declaration to the effect that the firm is registered under the Sales Tax Department alongwith Photostat copy of the latest income tax clearance certificate.

Encl: As above



Telephones:
Off.(PBX) : 0184-2291119,
 : 2291519 , 2291218
Fax : 91-184-2290480
E-mail-directr@cssri.ren.nic.in

केन्द्रीय मृदा लवणता अनुसंधान संस्थान,
करनाल (हरियाणा), भारत
Central Soil Salinity Research Institute,
Karnal- 132 001 (Haryana) INDIA

**PARTICULARS FOR SUPPLY , INSTALLATION, TESTING AND
COMMISSIONING OF 8 PASSENGERS CAPACITY LIFT
AT CSSRI, KARNAL – 132 001 (HARYANA)**

- 1 Tender is invited for Supply, installation, testing and commissioning of 8 Passengers capacity lift in the Laboratory Building at CSSRI, Karnal
2. The lift to be installed at Lab building, from ground to 3rd floor
- 3 The dismantled material of the existing goods lift will be retained by the firm and accordingly credit towards dismantled material will be considered while quoting the rate.
4. The firms are requested to visit the site to ascertain the work and work site (if desired) before quoting the rates.
- 5 The proposal should be submitted in two envelopes
 - A. Technical bid.
 - B. Financial bid.

Technical bid should include the detail of works of similar nature Undertaken by the firm

Work completion schedule etc.